Bill of Quantities (BOQ)

Jankalyan Aa Bi Korti bhawan nirman ,kumakh 4

IFB No.: KRM/NCB/W/03/2083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss or damage to works, plant, material, equipment, property, Contractor's employees and labour, Employer's and Consultant's staff, personnel injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract all complete.	PS	1.00	26,000.00 Twenty-six thousand rupees only.	26,000.00 Twenty-six thousand rupees only.
PS.2	Carry out Lab test as per specification and as directed by site Engineer all complete	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.3	Providing and installation of project signboards with required size with excavation , placing, installing, concreting all completet as per specification and instruction of engineer.	PS	1.00	6,140.00 Six thousand one hundred forty rupees only.	6,140.00 Six thousand one hundred forty rupees only.
	Total provisional sums				52,140.00 Fifty-two thousand one hundred forty rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earth work excavation in foundation in clay & silty soft soil lead upto 10 mtr. & lift 1.5 mtr for foundation manually	cum	43.69125			
1.2	'Earth back filling in foundation trenches & floor in 150 mm thick layers with sprinkling water, ramming & consolidating (using the soil received from the same site) as per specification and as directed by Engineer.	cum	13.107375			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of Boulder soling with sand packing the joint and watering including dressing of base up to the approved levels as specification and as directed by Engineer.	cum	28.993122			
1.4	PCC (1:2:4) M15 Works in foundation and floor base including haulage, supply of materials, fixing the form works, supply of required labours all complete as per drawing, Specification and as directed by Engineer.	cum	16.705125			
1.5	PCC (1:1.5:3)-M20 For RCC Works in super structures, deck slabs, beams, columns including haulage, supply of materials, supply of required labours all complete as per drawing, Specification and as directed by Engineer.	cum	69.02159			
1.6	Random Rubble Stone Masonary Work in 1:6 in cement sand Mortar in perfect line and level as per specification and as directed by Engineer.	cum	19.29			
1.7	First class Brick work in Super structure in 1:4 c/s mortar with approved quality bricks in line & level with necessary scaffolding, wetting the bricks, proper packing the joints & curing the works with all complete as per drawings , specification and as directed by Engineer.	cum	1.127			
1.8	Formwork for centering & shuttering for RCC works in sub and super-structures with approved material such as plywood(19mm th.), local wood etc.with necessary props, staging & removal of forms all complete as per drawings, specifications and as directed by Engineer.	sqm	494.581499			
1.9	Fixing Torsteel/TMT Reinforcement Grade-1 (Fe 500) conforming to I.S. 1786-1985 in R.C.C. work including cleaning, cutting, bending, placing in position on the basis of drawings, specifications, etc. Approved and tested Brands.	KG	8,056.63			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.10	Installation , concealed wiring and earthing by using genuine materials and PVC pipe with switch ,switch board ,ceiling rose ,2*22 NS standard cu wire et for light & fan point as required , all complete electrical works as per specifications & as directed by site Engineer	point	26.00			
1.11	75 mm diameter PVC pipe for the rain water draining	rm	18.00			

Total Item Price	
VAT (13.00%)	
Grand Total	