Bill of Quantities (BOQ)

Construction, Renovation, Interior Decoration, Furnishing, Supply & Installation Works for University Conference Hall

IFB No.: 3500057055/LTU/W/NCB-01/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of work,equipement,contractors workmen and employees and third party insurance against damage to other person and properties.	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.2	Supply and erection of Information Sign board 1200x900 mm size including full compensation for labour, materials, transoprtation and other incidental all complete.	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				12,000.00 Twelve thousand rupees only.

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Fabricating, supplying & fixing of different size M.S. black pipe Truss with metal primer for Stage.	Kg	563.18			
1.2	Waterproof Plywood (19mm) For stage	Sqm	37.31			
1.3	Brick masonry work in (1:4) cement , sand mortar in second floor with approved quality first class chimney made bricks in perfect line and level including wetting the bricks, packing the joints and curing, with necessary scafolding work, including supplying of all materials, labaour , lead and lift, Work all complete as per design, drawing, specification and approval site engineer.	Cum	2.04			
1.4	12.5 mm. thick cement sand plaster work 1:4 on wall.	Sqm	40.73			
1.5	Two coat white cement paint painting work .	Sqm	40.73			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	PCC work on wall (cement concrete) including supply of materials and haulage distance upto P.C.C.(1:2:4) with crushed aggregate	Sqm	0.09			
1.7	RCC work of grade M20 (1:1.5:3) including material and labour requried for mixing, placing in position, vibrating, compacting, finishing, curing and all other incidentals required to produce concrete of specified strength.	Cum	0.07			
1.8	Tor steel reinforcement bar of fe 415/500 grade including straightening, cleaning, cutting, binding and fixing in position with annealed tying binding wire as per drawing, design and intruction all complete.	Kg	60.51			
1.9	Form work shuttering & centering with (USED 12mm PLY WOOD and MS Black Pipe) all complete	Sqm	1.36			
1.10	Supply, installation, testing and commissioning of 4.0 TR (48,000 BTU/hr) ceiling cassette type split air conditioner, complete with indoor and outdoor units, copper refrigerant piping with insulation, drain piping, electrical connection, remote control, supports and all necessary accessories.	Nos	3.00			
1.11	Heavy Sofa Set (Seat foam : 52 density foam 5 inch thickness (20x20),Back foam: 40 density foam 1 inch thickness,18 mm plywood & sisam wood use to construct frame of sofa.Used good quality Fabric swaith, 280 gsm 100% polyster.(Single Seater)	Nos	15.00			
1.12	Sofa set (Seat foam : 32 density foam 4 inch thickness (20x20),Used Good quality wood (size: 2"x1" & 3"x1") with 12mm plywood,Back foam: 32 density foam 1 inch thickness. Size (2+2+1) Seater)	Nos	2.00			
1.13	Highrange Carpet (Top Surface: Loop pile with embossed ring motif. Material: 10% Nylon (Durable, Stain-resistant,& suitable for high-traffic areas).Thickness 2.5mm, Wide 2 meter)	Rm	22.00			
1.14	UNO Carpet (Resilient Flooring , 20m length x 2m wide x 1.6mm thickness. Flexibility Shall not break, crack. PVC Material UNO Carpet)	Rm	80.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.15	Parda set (6x6) (2 pcs curtain high density polyester fabric. Fabric weight approx 600+GSM. Size (4x7)ft per pcs. 99.9%-100% light Opacity. Core temperature draft control (up to 5-7°C reduction). With 1 inch stainless steel curtain pipe & fancy steel braket & cap with installation charge)	Set	7.00			
1.16	Rustam (Material: 17mm partical board. Integrated cable management, gooseneck microphone mounts, shelf storage. Size (4.5)ft)	Set	1.00			
1.17	Chair (1 inch pipe 100% SS, 1.9 mm patti, 10 mm ply, 4 inch foam 80 density, 350 GSM rexine.)	Nos	100.00			
1.18	Wooden Tea Table (Material: 17mm partical board. Low height center table.PVC edge banding along all exposed edge.Oval/Rectangular shape. Size (2x4)ft)	Nos	2.00			

Total Item Price	
VAT (13.00%)	
Grand Total	