Bill of Quantities (BOQ)

Kalika Satbari Tijuko Bot Sadak, Pokhara-28, Kaski

IFB No.: 3370139024/NCB/W/R/404/2083-084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document [GCC 19]	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Relocation of Services and repairing for existing infrastructure (houses, water supply pipes, HDPE pipes, Electric Poles, Temple, Foot staircase, Foot trail etc) as instructed by engineer's. [SSRBW Clause 105]	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				35,000.00 Thirty-five thousand rupees only.

General Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1m x1.2m (Board should be in Flex print with metal frame and both legs of the boards should be of black pipes with minimum diameter 1") as per instruction of Engineer.	Nos	1.00			

Earthworks and Construction Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil Mechanical Means (SSRB 907)	cum	184.90			

Earthworks and Construction Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications,as per the instruction of Engineer.(SSRB 3111)	cum	71.68			
2.3	Providing and laying Plum Concrete (Boulder Mixed Concrete) as per Drawing and Specifications 60% M15 concrete and 40% boulders/stone using Mechanical Means.(SSRB 3113)	cum	24.93			
2.4	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M20 (Including Formwork, including cost of core cutting) all complete as per drawing and technical specification (SSRB 2000)	cum	77.91			
2.5	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications (SSRB 2014)	Kg	3,669.06			

Total Item Price	
VAT (13.00%)	
Grand Total	