Bill of Quantities (BOQ)

Saptari District surunga na.paa. ward no. 5 mahendra rajmarga dekhi kushaha birnagar jane bato pakki sadak dhalan karya.

IFB No.: 3370115012/IFB-1-083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Supplying and erecting Project sign board with Size 1.80mx1.20m at site all complete as per specification and instruction of Site engineer..	PS	1.00	6,283.60 Six thousand two hundred eighty-three rupees and sixty paisa only.	6,283.60 Six thousand two hundred eighty-three rupees and sixty paisa only.
PS.2	Insurance for loss or damage to works, plant, materials, equipment property, labour and personnel injury or death including third party up to end of mantenence period of work as per condion of cotract.	PS	1.00	60,000.00 Sixty thousand rupees only.	60,000.00 Sixty thousand rupees only.
PS.3	Provide , Operate, and maintain Quality Control Laboratory including Quality Control , Engineering Equipment , Accessories and Consumables for both field testing facilities and off side test as per specifications and as instructed by engineer	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				1,16,283.60 One lakh sixteen thousand two hundred eighty-three rupees and sixty paisa only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications.	m^2	1,326.99			
1.2	E/W Excavation in foundation for Nali	m^3	31.20			
1.3	Stone Soling in Nali Foundation	m^3	5.20			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of Plain/Reinforced Cement Concrete Grade M 15 in Nali Foundation including formwork all complete as per Drawing and Technical Specifications	m^3	5.20			
1.5	Providing , laying ,spreading Granular Sub-Base Material by Mechanical means on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications.	m^3	199.05			
1.6	Providing and laying of Plain/Reinforced Cement Concrete Grade M 20 including formwork all complete as per Drawing and Technical Specifications	m^3	222.45			
1.7	Providing , Cutting , bending, placing, binding & fixing in position reinforcement for RCC works as per Drawing and Technical Specifications all complete	Kg	12,029.32			
1.8	Providing and Laying of 12mm Plywood for construction joints all complete as instructed by Site engineer.	m^2	33.17			

Total Item Price	
VAT (13.00%)	
Grand Total	