Bill of Quantities (BOQ)

Sarbajanik Gheching gumbama purbadhar Nirman,Gheching Gumba Sunwal 8,Bairagnath Mandir ,Sunwal-08.

IFB No.: 80547403/16.SUN/NCB/2083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document	P/S	1.00	17,500.00 Seventeen thousand five hundred rupees only.	17,500.00 Seventeen thousand five hundred rupees only.
PS.2	Necessary Lab Test Work for official purpose.(Regular reports for Quality Assurance of work done shall be under Contractor responsibility)	P/S	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	Supply & Installation of Project Information boards as per instructed by site engineer.	L/S	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
PS.4	Other Unseen Miscellenous Works as per approval. (Work Shall be done only on approval of the workorder by client as per approved norms and the payment of this item will be done according to submitted original copy ofrelated invoices)	P/S	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				39,500.00 Thirty-nine thousand five hundred rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing Grass and Removal of Rubbish and Dressing and levelling the construction surface Clearing grass/ top soil and removal up to a distance of 50 meters outside the periphery of the area , including cutting and filling of small undulation. By Manual Means	Sqm	504.60			
1.2	Earthwork in excavation for foundation in Ordinary soil by using mechanical means including necessary lead and lift.	Cum	66.756			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and Stone soiling in foundation and floor as per drawings, specification and instruction of the consultant/Engineer, all complete.	Cum	19.8172			
1.4	Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:3:6 (1 cement : 3 sand : 6 coarse aggregate) . all complete as per drawings, specifications and the instructions of the Engineer.	Cum	16.2553			
1.5	Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:2:4 (1 cement : 2 sand : 4 coarse aggregate) for leveling course in foundations and floor of building, pathway, etc in all level with stone aggregate of size not more than 25 mm of approved quality dewatering, batching, mixing, transporting, placing, compacting with vibrator, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.	Cum	6.47961			
1.6	Providing and laying first class chimney fired brick one or more brick thick wall in cement mortar 1:6 (1 cement : 6 coarse sand) in foundation up to plinth, Sub-structure & super structure and other specified places in all heights and level including the cost of single or multi stage scaffolding, soaking bricks, curing, raking joints, provision for recesses, openings, toothing etc., all complete as per drawing, specifications and instructions of the Engineer.	Cum	8.37223			
1.7	Providing and laying stone masonary wall in cement mortar 1:6 (1 cement : 6coarse sand) in Sub-Structure as well as superstructure and other specified places in all heights and level including the cost of single or multi stage self standing scaffolding, curing, raking joints, provision for recesses, openings, toothing etc., all complete as per drawing, specifications and instructions of the Engineer.	Cum	22.5144			
1.8	Providing, laying & curing 12.5 mm thick cement sand (1:6) plastering in Brick masonary walls/Stone masonary wall ceiling, beams surfaces including chipping & wetting the concrete surfaces finished in perfect plumb, lines and level as per drawings, specifications and instructions of the site engineer.	Sqm	208.692			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.9	Providing and laying MS Pipe for Truss with one coat primer and two coat Enamel Paint All complete as per instruction of site Engineer	Kg	2,375.75997			
1.10	MS Pipe Work with one coat primer and enamel painting as per drawing and instruction of site engineer	Kg	399.29			
1.11	Supply and fitting of 0.41mm Colored CGI sheet roofing including fixing in proper shape & size with all necessary rails, screws, bolts & nuts washers, J & L hoocks/Screws etc as per drawing & instruction all complete.	Sqm	176.7378			
1.12	Providing, folding to required shape and fixing in position pain sheet of 0.41mm thick prefinished ridge width cover of required shape and size with all required fixing accessories like self drilling/tapping screws, clips, clamps, washer etc., all complete as per drawings, specifications and instructions of the Engineer.	Rm	18.60			
1.13	Heavy Coated Gabion wire chain link fencing with mesh size 3"x3" 10 gauge	Sqm	187.50			
1.14	Providing,Laying 60 mm Interlocking Tiles (Local made) binded with Crusher Stone Dust including fitting and laid over 50mm thick Crusher Stone Dust as directed by Site Engineer	Sqm	100.00			

Total Item Price	
VAT (13.00%)	
Grand Total	