Bill of Quantities (BOQ)

Road Upgrading work from Adharbhut Secondary School (Nikas) to Balanghar Rampur-7, Road Upgrading Work from Phediya Dhara to Tersa -Rampur-7, Road Upgrading Work from Paschim Pyakaluk Chaupari Rampur Ward No. 6 to Samara and Road Upgrading and

IFB No.: 3470150015/UDBOP-NCB-083/84-10

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	27,200.00 Twenty-seven thousand two hundred rupees only.	27,200.00 Twenty-seven thousand two hundred rupees only.
PS.2	Material Tests	PS	1.00	9,492.00 Nine thousand four hundred ninety-two rupees only.	9,492.00 Nine thousand four hundred ninety-two rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	4,000.00 Four thousand rupees only.	4,000.00 Four thousand rupees only.
	Total provisional sums				40,692.00 Forty thousand six hundred ninety-two rupees only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum.	98.25			
1.2	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum.	114.95			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying Reinforcement Cement Concrete RCC(GradeM20)Including batching , mixing, transporting,placing, vibrating ,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum.	34.50			
1.4	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	Kg	1,135.80			
1.5	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum.	300.39			
1.6	Providing and laying of PCC 1:2:4 (Grade M 15) in foundation complete as per Drawing and Technical Specifications	cum.	53.63			
1.7	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% Boulders/stones Mechanically with formwork (water proof ply wood or equivalent material).	cum.	136.13			

Total Item Price	
VAT (13.00%)	
Grand Total	