Bill of Quantities (BOQ)

Upgrading of Kailash Path Tilottama 05, Rupandehi

IFB No.: 3370148025/RIDO/RUP/134/NCB/083-084/97

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.	LS	1.00			
1.3	Supply and place standard size sign board for contract information.	Nos	1.00			
1.4	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cu.m	85.02			
1.5	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cu.m	40.38			
1.1	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications,(Including Formwork)PCC Grade M 15	Cu.m	13.46			
1.6	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications,(Including Formwork) PCC Grade M 20	Cu.m	94.93			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	kg	5,095.52			

Total Item Price	
VAT (13.00%)	
Grand Total	