Bill of Quantities (BOQ)

Upgrading of Simrutu-Khumcheri-Dalsinge Road

IFB No.: 80659501300/TRM/SKD/NCB/R/02/2083/084(RE)

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss or damage to works, pant, material, equiment, property, contractor's emloyees and labour, employer's and consultants's staff personnal injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract	ps	1.00	1,00,000.00 One lakh rupees only.	1,00,000.00 One lakh rupees only.
PS.2	Provide and installation of project information board including excavation, concreting , back filling etc. all complete as per DoR standard specification for road	ps	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	Provision of laboratory tests as required (Cement, Reinforcement, Sand, Brick, Aggregate etc) and other lab tests like seive, utm, cube mould, slump testing as per the specification and instructions of the Site Engineers.	ps	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
	Total provisional sums				1,50,000.00 One lakh fifty thousand rupees only.

Works for complete or part construction and civil engineering work CPV: 45200000-9 - Works for complete or part construction and civil engineering work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork Excavation in cutting., Roadway excavation in ALL TYPE OF SOIL,ORDINARY ROCK AND HARD ROCK by Mechanical means, as per drawing and technical specifications including disposalat safe site up removal all lift and lead as per of stumps and other deteterious matter, all lifts drawing and instruction of the site engineer.	cum	1,003.04			
1.2	Earthwork Excavation in Foundation excavation in ALL TYPE OF SOIL AND ORDINARY ROCK by Mechanical means, as per drawing and technical specifications including removal of stumps and other deteterious matter, all lifts and lead as per drawing and instruction of the site engineer.	cum	60.00			

Works for complete or part construction and civil engineering work CPV: 45200000-9 - Works for complete or part construction and civil engineering work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Plum Concrete works in 40%/60% mass concrete, including Boulder cleaning work (P.C.C in 1:2:4) 60% & 40% boulder stone	cum	111.62			
1.4	Providing and plain cement concrete M15(1:2:4) including placing compacting and testing etc all complete as per specification and instruction of the site engineer.	cum	252.00			
1.5	Bar bending ,binding ,cutting placing etc ,all complete for RCC work etc all complete as per specification and instruction of the site engineer.	kg	7,410.43			
1.6	Providing and laying of dry stone solling for foundation works of all complete as per specificationand instruction of the site engineer.	cum	260.40			
1.7	Form Work For Wooden Form Work all complete etc all complete as per specification and instruction of the site engineer.	sqm	30.00			

Total Item Price	
VAT (13.00%)	
Grand Total	