Bill of Quantities (BOQ)

Upgrading of Sarkuwa Dandamadhi Nayakhum Pahi Road Jaimini Municipality-04 Baglung

IFB No.: 3370145034/IDOBAGLUNG/NCB/W/R/64/2083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property as per GCC clause 13.	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.2	Relocation for public utilities such as Electric Pole,Irrigation pipe ,water supply,Skilled ,Unskilled Man Power & Other Unseen Works .	PS	1.00	22,000.00 Twenty-two thousand rupees only.	22,000.00 Twenty-two thousand rupees only.
	Total provisional sums				42,000.00 Forty-two thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m having details of contract in the format and wording as directed by the Engineer.(SSRBW 110)	Nos	1.00			

Works for complete or part construction and civil engineering work CPV: 45200000-9 - Works for complete or part construction and civil engineering work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Road way Excavation in all types of soil,ordinary rock & hard rock as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.(SSRBW 9050	Cu.m	7,747.50			

Works for complete or part construction and civil engineering work
CPV: 45200000-9 - Works for complete or part construction and civil engineering work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
2.2	Removal of Unserviceable soil including excavation, loading and disposal up to 1000 m lead	Cu.m	1,316.25			
2.3	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil Mechanical Means (SSRBW 907)	Cu.m	33.75			
2.4	Providing and laying of hand pack Stone soling and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.(SSRBW1006)	Cum	10.12			
2.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork,Curring,Testing)(SSRBW2000)	Cum	6.75			
2.6	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification.(Icluding Curring,Testing, HDPE Pipe Weep holes) Machine Mixed Mortar(SSRBW2600,2607)	Cum	107.25			
2.7	Providing and Pointing with cement mortar on masonry work in structure as per Technical Specifications (cement mortar 1:3)(2600,2607)	Sqm	107.25			

Total Item Price	
VAT (13.00%)	
Grand Total	