Bill of Quantities (BOQ)

Roadway Excavation Works in Bhairabsthan Mandir To Mauribhir Kavre Ramtola Rayandanda Road Baglung Municipality-12 Baglung

IFB No.: 3370145034/IDOBAGLUNG/NCB/W/R/63/2083/84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property as per GCC clause 13.	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.2	Relocation for public utilities such as Electric Pole,Irrigation pipe ,water supply,Skilled ,Unskilled Man Power & Other Unseen Works .	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
	Total provisional sums				40,000.00 Forty thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m having details of contract in the format and wording as directed by the Engineer.(SSRBW 110)	Nos	1.00			

Works for complete or part construction and civil engineering work
CPV: 45200000-9 - Works for complete or part construction and civil engineering work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
2.1	Road way Excavation in all types of soil,ordinary rock & hard rock as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.(SSRBW 9050	Cu.m	10,462.50			

Works for complete or part construction and civil engineering work
CPV: 45200000-9 - Works for complete or part construction and civil engineering work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
2.2	Removal of Unserviceable soil including excavation, loading and disposal up to 1000 m lead	Cu.m	546.75			
2.3	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil Mechanical Means (SSRBW 907)	Cu.m	75.00			
2.4	Supply of machine made hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diapharagms, with binding wire x swg, mesh wire 3mm and selvedged wire 3.9 mm and lacing wire 2.4 mm, including palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification.(SSRBW2401,2402)	Cum	112.50			
2.5	Providing, laying and fixing of Geo-textile (filter fabrics), all complete as per specification.(SSRBW 2404)	Sqm	75.00			

Total Item Price	
VAT (13.00%)	
Grand Total	