## Bill of Quantities (BOQ)

### Construction of Irrigation Canals and Procurement and Installation of Motors and HDPE Pipes in Different Toles of Parshuram -07, Dadeldhura.

IFB No.: 80775402300/05/WORKS/NCB/ PM/2083/084

| Provisional Sum | | | | | |
|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Unit Rate (NPR)** | **Amount (NPR)** |
| PS.1 | Items Not Covered By BoQ or Provisional Sum | PS | 1.00 | 48,000.00<br>Forty-eight thousand rupees only. | 48,000.00<br>Forty-eight thousand rupees only. |
| | **Total provisional sums** | | | | 48,000.00<br>Forty-eight thousand rupees only. |

| Construction work<br>CPV: 45000000-7 - Construction work | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.1 | Earthwork in excavation in Boulder mixed and Soft soil in foundation, trenches including timbering and shoring & 30m Lead and 1.5 m. lift all complete as per design, drawing and specification. | Cu.m | 15.63 | | | |
| 1.2 | Stone soling work in foundation and floors with supplying of approved quality of stone laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification. | Cu.m | 14.63 | | | |
| 1.3 | P.C.C.(1:2:4 ) for P.C.C.work in foundation, columns, beams, slabs, lintels etc. with cement, sand, and crushed stone aggregate of size less than 20mm including mixing with concrete mixture, compacting the concrete with vibrator machine, laying, finishing to approved level ,lines and dimensions and curing all complete nett. | Cu.m | 16.11 | | | |
| 1.4 | Formwork with approved materials for all works necessary propping, scaffoldong, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for Column/Slab/Beam etc. complete work | Sq.m | 41.54 | | | |
| 1.5 | HDPE Pipe | Kg | 1,675.23 | | | |

| Construction work<br>CPV: 45000000-7 - Construction work | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.6 | 2 HP Submersible Pump & Motor with Panel Board Indian Standard company | Nos | 1.00 | | | |
| 1.7 | 5 HP Submersible Pump & Motor with Panel Board Indian Standard company | Nos | 3.00 | | | |
| 1.8 | 3 HP Submersible Pump & Motor with Panel Board Indian Standard company | Nos | 2.00 | | | |
| 1.9 | MCB 30 Ampere | Nos | 6.00 | | | |
| 1.10 | Pipe Fitting (Tee, Bond, Nipple, Reducer) | Job | 6.00 | | | |
| 1.11 | Electrical Service Wire Cable | mtr | 650.00 | | | |
| 1.12 | Submersible Cable 2.5mm squre | mtr | 500.00 | | | |

| | |
|---|---|
| **Total Item Price** | |
| VAT (13.00%) | |
| **Grand Total** | |