Bill of Quantities (BOQ)

Maintenance Works of Bardahawa,Jinuwa,Bhartapur ,Sadak. Ward 9

IFB No.: BMO/BMO/16/NCB/WORKS/83-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply and placing project information board/hoarding board ,carryout necessary Insurance ,lab test and photography of work,event and material as per requirement and instruction ,all complete	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing of grass, removing roots breaking sods, levelling the surface and disposal all complete.	Sqm	1,846.00			
1.2	Scarifying the existing bitumunous road surface by mechanical means to a depth of 50 mm,pulverizing/mixing the scarified material as required,and preparing the surface for recycling/reconstruction as per Drawing and Technical Specification .	Sqm	1,000.00			
1.3	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing, watering and compacting to form a layer of base course as per Drawing and technical Specifications. [1204]	m3	110.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and Applying Prime coat with hot bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying at specified rate as per the Technical Specification. [1302] Engineer.	ltr	1,980.00			
1.5	Providing and Applying Tack coat with hot bitumen at specified rate on the prepared surfaces including cleaning as per the Technical Specification. [1302]	ltr	1,846.00			
1.6	Providing, mixing, and laying asphalt concrete with compaction.[1309]	m3	110.76			

Total Item Price	
VAT (13.00%)	
Grand Total	