# Bill of Quantities (BOQ)

## Sirancheri Kafal Bot Jardhare Hudai Hile Sadak, Kakani RM 4, Nuwakot

IFB No.: IDONUWAKOT/W/NCB/12/2083-84

**Provisional Sum**

| SL. No. | Item Description | Unit | Quantity | Unit Rate (NPR) | Amount (NPR) |
|---|---|---|---|---|---|
| PS.1 | Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property(GCC 13) | PS | 1.00 | 50,000.00<br>Fifty thousand rupees only. | 50,000.00<br>Fifty thousand rupees only. |
| PS.2 | Carry out additional tests for material and works as required and instructed by the Project Manager.(GCC 33.1) | PS | 1.00 | 10,000.00<br>Ten thousand rupees only. | 10,000.00<br>Ten thousand rupees only. |
| PS.3 | Provide and maintain traffic safety, Occupation Health and Safety (OHS) as per special provision,control measures and temporary diversions during construction as instructed by the Engineer.(DoR SS 104) | PS | 1.00 | 20,000.00<br>Twenty thousand rupees only. | 20,000.00<br>Twenty thousand rupees only. |
| | **Total provisional sums** | | | | 80,000.00<br>Eighty thousand rupees only. |

**Construction work**
**CPV: 45000000-7 - Construction work**

| SL. No. | Item Description | Unit | Quantity | Bidder's Rate (NPR) | Bidder's Rate (in words) | Total Amount (NPR) |
|---|---|---|---|---|---|---|
| 1.1 | Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works.(DoR SS 110) | No | 1.00 | | | |
| 1.2 | Earthwork in excavation of Foundation of structures for all types of soil , including construction of shorring and bracing, removal of stumps and other deleterious matter and backfilling with aproved materials as per drawing and technical specification.(DoR SS 907) | Cum | 303.33 | | | |

| Construction work<br>CPV: 45000000-7 - Construction work | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.3 | Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.( DoR SS 1006) | Cum | 205.07 | | | |
| 1.4 | Providing and laying of Plain/Reinforced Cement Concrete M20 (1:1.5:3) Including Formworks in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000) | Cum | 265.00 | | | |
| 1.5 | Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification(DoR SS 2014) | MT | 8.34 | | | |
| 1.6 | Providing and laying of Random Rubble Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2602,,2603) | Cum | 89.57 | | | |
| 1.7 | Providing and laying of Plain Cement Concrete M 10 ( or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000) | Cum | 4.22 | | | |

| | |
|---|---|
| **Total Item Price** | |
| VAT (13.00%) | |
| **Grand Total** | |