## Bill of Quantities (BOQ)

### Ward No. 1 Bagha Pokhariko Adhuro Mandir.

IFB No.: RRM/2083-84/NCB/Works/06

**Provisional Sum**

| SL. No. | Item Description | Unit | Quantity | Unit Rate (NPR) | Amount (NPR) |
|---|---|---|---|---|---|
| PS.1 | Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property. | PS | 1.00 | 25,000.00<br>Twenty-five thousand rupees only. | 25,000.00<br>Twenty-five thousand rupees only. |
| PS.2 | Provision for carrying out additional test for material and works as required and instructed by the site engineer. | PS | 1.00 | 10,000.00<br>Ten thousand rupees only. | 10,000.00<br>Ten thousand rupees only. |
| PS.3 | All necessary electrical accessories such as point,screw, tape,Pvc Box,hdpe pipe,etc. including electrical wiring charge all Complete. | PS | 1.00 | 25,000.00<br>Twenty-five thousand rupees only. | 25,000.00<br>Twenty-five thousand rupees only. |
| | **Total provisional sums** | | | | 60,000.00<br>Sixty thousand rupees only. |

**Construction work**
**CPV: 45000000-7 - Construction work**

| SL. No. | Item Description | Unit | Quantity | Bidder's Rate (NPR) | Bidder's Rate (in words) | Total Amount (NPR) |
|---|---|---|---|---|---|---|
| 1.1 | Project Information Board as Specified By Site Engineer | Nos | 1.00 | | | |
| 1.2 | Providing and laying of PCC For RCC (Grade M 20) as per Drawing and Technical Specification. | Cum | 33.65 | | | |
| 1.3 | Providing and laying,Fitting and placing HYSD bar Reinforcement as per Drawing and Technical Specification. | Kg | 3,217.16 | | | |
| 1.4 | Providing, Preparing and Installing form work including necessary supports and removing after completion as per Drawing and Technical Specifications | Sqm | 284.74 | | | |

| Construction work<br>CPV: 45000000-7 - Construction work | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.5 | Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:6) all complete as per Drawing and Technical Specifications | Cum | 11.55 | | | |
| 1.6 | Providing and applying Double Coat Bitumen Paint works in structure as per Drawing and Technical Specifications | Sqm | 98.00 | | | |
| 1.7 | Providing and applying 12.5 mm thick Plaster with Cement mortar (cement:sand 1:4) on brickwork in structure as per Drawing and Technical Specifications | Sqm | 273.19 | | | |

| | |
|---|---|
| **Total Item Price** | |
| VAT (13.00%) | |
| **Grand Total** | |