Bill of Quantities (BOQ)

Bhabisya Nirman Ma Vi Devdaha-2 Dhekawanko Bhawan Nirman, Rupandehi

IFB No.: 3500048075/SDDO/NCB-01/083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Installation of Project Signboard of proper dimensions, complete as directed by the Engineer.	No.	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
PS.2	Additional Quality Control Tests beyond routine tests and other Unforeseen Works, when considered necessary by the Engineer.	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.3	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property.	PS	1.00	31,431.62 Thirty-one thousand four hundred thirty-one rupees and sixty-two paisa only.	31,431.62 Thirty-one thousand four hundred thirty-one rupees and sixty-two paisa only.
	Total provisional sums				39,431.62 Thirty-nine thousand four hundred thirty-one rupees and sixty-two paisa only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions (including addition of PVC/HDPE pipes for Electrical Conduits with necessary electrical boxes and sockets) all complete as per specifications, drawings and instructions of the site engineer, all complete.	cum	50.06			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Providing,Supplying laying & Centering and shuttering with plywood for Column, Beam, Slab & other RCC work including all necessary propping, scaffolding, staging, supporting, dismantling and clearing from the site, including shuttering all complete as per design drawings, specifications and instruction of the site engineer .	sqm	458.94			
1.3	Providing,Supplying ,Cutting and laying Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation, column, beam, wall, staircase, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	kg	7,978.89			
1.4	Providing, laying, compacting and curing plain cement concrete M15 (1:2:4) with opc cement, sand and well graded crushed stone aggregate finishing to approved level, lines and dimensions all complete as per drawings, specification.	cum	3.27			
1.5	Providing, laying and curing first class brick masonry works for Sub-Structures/super Str in cement, sand mortar (1:6) in perfect lines & level as per specification, drawings & instructions of the site engineer.	cum	50.29			
1.6	Supply, fixing and fitting iron bars,angle,pipe,sheet etc. for door & windows with primer coat and 1 coat of redoxide paint with proper finishing all complete as per instruction of site engineer.	kg	2,097.00			
1.7	Providing and supplying MS pipes, angle of various sizes for truss section in perfect line and level Metal Works with 1coat of redoxide paint over metal Surface , all complete as per specification, and instruction of site engineer	kg	89.88			
1.8	Providing & supplying Heavy CGI Sheet 0.45 mm thick with fitting all set complete as per specification, and instruction of site engineer.	sqm	28.89			

Total Item Price	
VAT (13.00%)	
Grand Total	