Bill of Quantities (BOQ)

Blacktopping of Saunbade Tole Pipal Chautara Hudai Bichtole Samma, Bi. Na. Pa. -09, Surkhet

IFB No.: 3370168016/02-IDO/SKT/W/NCB/13/083-084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss or damage to works, plant, material, equipment, property, Contractor's employees and labour, Employer's and Consultants's staff personnel injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by the Project Manager.	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
	Total provisional sums				90,000.00 Ninety thousand rupees only.

General Item

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specifixcation for Road and Bridge Works.	Nos	1.00			

Pavement Works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
2.1	Scarifying Existing road Surface to a depth 50 mm and disposal of scarified material with in all lifts and lead as per Drawing and Technical Specifications.	Sq.M.	2,004.50			

Pavement Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.2	Providing and laying natural granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications., By Mechanical means.	Cum	34.50			
2.3	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of Base course as per Drawing and Technical Specifications. all complete.	Cum	300.67			
2.4	Prime Coat, Prime Coat, with MC 30 / 70 by Mechanical Means, Providing and applying prime coat with Hot Bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying by mechanical means as per Technical S	Ltr	1,603.60			
2.5	Tack Coat, Tack coat with Bitumen By Mechanical Means, Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation., all complete.	Ltr	1,102.50			
2.6	Providing and laying bituminous concrete/asphalt concrete using crushed aggregate of specified grading, premixed with bituminous binder and filler as per drawing and technical specification.	Cum	63.00			

Total Item Price	
VAT (13.00%)	
Grand Total	