Bill of Quantities (BOQ)

Upgrading of Road Connecting Janabhawan Jordhara Setidevi to Deumai Municipality , Ilam Municipality 6

IFB No.: 3370103011/IDOILAM/NCB/W/13/83/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for loss or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data and technical specifiation (Cl. 19 of CoC)	PS	1.00	56,000.00 Fifty-six thousand rupees only.	56,000.00 Fifty-six thousand rupees only.
PS.2	Carrying out laboratory and field tests on materials and completed works, as required and as directed by the Engineer, including all necessary arrangements and incidental works, complete.	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.3	Providing, writing and installation of the project information board as per the Standard Specifications and approved drawings and as instructed by the Engineer.	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				78,000.00 Seventy-eight thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil by Mechanical means upto 3m depth	Cum.	356.80			
1.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum.	184.98			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of Reinforced Cement Concrete in Foundation complete INCLUDING FORMWORK as per Drawing and Technical Specifications. RCC Grade M 20	Cum.	109.08			
1.4	Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification.	Tonne	6.9084			
1.5	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% boulders/stones using Mechanical Aids	Cum.	150.07			
1.6	Providing and laying of Plain Cement Concrete M 10 (or1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.	Cum.	2.22			
1.7	Providing and laying of Stone Masonry Work in Cement Mortar 1:6 in Foundation complete as per Drawing and Technical Specifications..	Cum.	32.72			
1.8	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete INCLUDING FORMWORK as per Drawing and Technical Specifications. PCC Grade M 15	Cum.	12.32			

Total Item Price	
VAT (13.00%)	
Grand Total	