Bill of Quantities (BOQ)

Upgrading Of Shiva Mandir Jarangbesi Road, Ba Su-08, Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/25/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[GCC19]	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Reallocation of services and minor infrastructures and Environment Protection Work as per specification and as instructed by the Project Manager.[SP/SS-111]	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
	Total provisional sums				80,000.00 Eighty thousand rupees only.

Road Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SSRBW 110]	Nos	1.00			
1.2	Road way Excavation in all types of soil, Ordinary Rock & hard Rock(using Breaker) as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. [SSRBW 905]	Cum	1,323.91			
1.3	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SSRBW 2602,2603,2607].	Cum	123.75			
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SSRBW 1006].	Cum	119.41			

Road Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork) [SSRBW: 2000]	Cum	68.78			
1.6	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork) [SSRBW: 2000]	Cum	66.93			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications [SSRBW: 2014]	KG	2,741.51			
1.8	Supply of machine made hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diapharagms, with binding wire x swg, mesh wire 3mm and selvedged wire 3.9 mm and lacing wire 2.4 mm, including palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification [SSRBW 2401,2402].	Cum	58.50			
1.9	Providing, laying and fixing of Geo-textile (filter fabrics), lead 30m [SSRBW 2404]	Sqm	39.00			

Total Item Price	
VAT (13.00%)	
Grand Total	