Bill of Quantities (BOQ)

Maintenance Of Hirapur-Farsatikar Road,ward 2

IFB No.: 50806/50806/NCB/SRM/13/083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Carry out additional tests for material and works as required and instructed by the Engineer. ,unforeseen works & Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property.	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
	Total provisional sums				40,000.00 Forty thousand rupees only.

Road-maintenance works CPV: 45233141-9 - Road-maintenance works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	supply and fitting of 3'x4' Hoarding board,diversion boards including letter as per instruction of site engineer.	nos.	2.00			
1.2	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications. Lead upto 30m.	sq.m.	868.10			
1.3	Crusher Run Macadam Base. Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of Base course as per Drawing and Technical Specifications. By Mix in palce method.	cu.m.	112.81			
1.4	Providing and applying prime coat with hot bitumen MC 30/70 (including cutter)on prepared surface of granular base including cleaning of road surface and spraying at specified rate as per Technical specification.	sq.m.	3,358.10			

Road-maintenance works CPV: 45233141-9 - Road-maintenance works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation .	sq.m.	3,370.40			
1.6	"Providing and laying open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates as wearing course on a previously prepared base as per drawing an Technical Specifications.	cu.m.	67.40			

Total Item Price	
VAT (13.00%)	
Grand Total	