Bill of Quantities (BOQ)

Upgrading of Bansghari Dahar to Khet Puchhar – Khadalni Road, Kushma -9, Parbat

IFB No.: 3370142014/IDOP/NCB/W/05/2083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, plants, materials, loss and damage to equipment, contractor's workmen and employees and third party insurance against damage to other persons and property as per specifications and instructions of the engineer (GCC 19)	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Relocation of services and minor infrastructures as per specification and instructions of the engineer (SSRBW 105)	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				75,000.00 Seventy-five thousand rupees only.

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation of foundation of structures in all types of soil an rock by mechanical means, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 900, 907)	m^3	250.70			
1.2	Providing and laying of hand packed stone soling with 150 to 200 mm thick stones and packing with smaller stones on prepared surface as per drawings, technical specifications and instructions of the engineer (SSRBW 1000, 3111)	m^3	25.07			
1.3	Providing and laying of M15 PCC including formworks, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000)	m^3	8.72			

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying plum concrete including formworks (60% machine-mixed M15 concrete and 40% boulders / stone) including providing weep holes (not required in drain), all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2400, 2421)	m^3	163.50			
1.5	Providing and laying of M20 concrete for RCC including formworks, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000)	m^3	4.80			
1.6	Providing and laying, fitting and placing HYSD reinforcement, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000, 2014)	kg	170.30			

Total Item Price	
VAT (13.00%)	
Grand Total	