## Bill of Quantities (BOQ)

### Saptari chetra no 1 hanumannagar kankalini na.pa.8 sthit ramji suraitko ghar dekhi ward no.2 ko sima samma sadak dhalan, saptari chetra no.4 surunga na.pa.-3 karharwa dekhi mahuliya samma sadak dhalan.

IFB No.: 3370115012/IFB-01-083-084

| **Provisional Sum** | | | | | |
|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Unit Rate (NPR)** | **Amount (NPR)** |
| PS.1 | Insurance for the loss or damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as described in Condition of Contract . | PS | 1.00 | 68,000.00<br>Sixty-eight thousand rupees only. | 68,000.00<br>Sixty-eight thousand rupees only. |
| PS.2 | Provding, erection of project information board ( size: 1.8mx1.2m) in flex print , in 50mm dia tubular steel post, all complete | PS | 1.00 | 5,000.00<br>Five thousand rupees only. | 5,000.00<br>Five thousand rupees only. |
| PS.3 | Provide, operate and maintain quality control laboratory including quality control engineer equipment, accessories and consumables for both field testing facilities and off site test with manpower along with transportation facility for employer as per specification as instructed by engineer. | PS | 1.00 | 50,000.00<br>Fifty thousand rupees only. | 50,000.00<br>Fifty thousand rupees only. |
| | **Total provisional sums** | | | | 1,23,000.00<br>One lakh twenty-three thousand rupees only. |

| **Road construction works**<br>**CPV: 45233120-6 - Road construction works** | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.1 | Providing and laying Granular Sub-Base Material. By Mechanical means . Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. | cum | 307.995 | | | |

| Road construction works<br>CPV: 45233120-6 - Road construction works | | | | | | |
|---|---|---|---|---|---|---|
| **SL. No.** | **Item Description** | **Unit** | **Quantity** | **Bidder's Rate (NPR)** | **Bidder's Rate (in words)** | **Total Amount (NPR)** |
| 1.2 | Scarifying Existing road Surface to a depth of 50 mm by Mechanical Means.Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications. | sqm | 2,153.30 | | | |
| 1.3 | Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.including formwork Grade M 20 | cum. | 322.995 | | | |
| 1.4 | Providing and laying , fitting and placing un-coated reinforcement complete in Superstructure as per drawing and technical specification and Engineers instructions all complete.(SS-2014) | Kg | 17,265.309 | | | |
| 1.5 | Providing 12mm Plywood for the use of construction joint all complete as instructed by Engineer. | Sqm | 53.833 | | | |

| | |
|---|---|
| **Total Item Price** | |
| VAT (13.00%) | |
| **Grand Total** | |