Bill of Quantities (BOQ)

Saptari District surunga 2 baaunna khola pakki pul dekhi raksajor pokhari hudai sisubari bhethat hotel jodne sadak kalopatre.

IFB No.: 3370115012/IFB-1-083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss or damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as described in Condition of Contract .	PS	1.00	65,000.00 Sixty-five thousand rupees only.	65,000.00 Sixty-five thousand rupees only.
PS.2	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer	PS	1.00	6,283.60 Six thousand two hundred eighty-three rupees and sixty paisa only.	6,283.60 Six thousand two hundred eighty-three rupees and sixty paisa only.
PS.3	Provide, operate and maintain quality control laboratory including quality control engineer equipment, accessories and consumables for both field testing facilities and off site test with manpower along with transportation facility for employer as per specification as instructed by engineer.	PS	1.00	70,000.00 Seventy thousand rupees only.	70,000.00 Seventy thousand rupees only.
PS.4	Carry out maintenance of the existing road/construction and traffic diversion to keep the road serviceable:as per specification (SS/SP-100) and instruction of engineer.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				1,91,283.60 One lakh ninety-one thousand two hundred eighty-three rupees and sixty paisa only.

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Compacting original ground supporting sub-grade Loosening of the ground upto a level of 500 mm below thesub-grade level, watered,	cum	307.865			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
	graded and compacted in layers asper Drawing and Technical Specifications.					
1.2	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications.	cum	726.5614			
1.3	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of sub-base/Base course as per Drawing and Technical Specifications.	cum	346.348125			
1.4	Providing and applying prime coat with Hot Bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying by mechanical means as per Technical Specification .Prime Coat, with MC 30 / 70 by Mechanical Means	Lit	2,078.08875			
1.5	Tack coat with Bitumen By Mechanical Means Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation	Lit	1,385.3925			
1.6	Bituminous Concrete / Asphalt Concrete Providing and laying Bituminous concrete/ Asphalt concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler as per Drawing and Technical Specifications and Engineers instructions all complete.(SS-1309)	cum	92.3595			

Total Item Price	
VAT (13.00%)	
Grand Total	