Bill of Quantities (BOQ)

Construction of the incomplete drain and laying of interlock blocks from Padam Bahadur Bhattarai's house to Pawan Rai's house

IFB No.: 1126215/03/SMO/SQ/W/2083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provisional sum for Lab test,hoding board and others as per site engineer.	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
	Total provisional sums				15,000.00 Fifteen thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearance work of stone from cement masonry wall & stacking of stone for re-used	cum	8.75			
1.2	Surface dressing work with cutting of raised soil & filling the ditches.	Sqm	648.00			
1.3	Earth work excavation in foundation in clay & silty soft soil lead upto 10 mtr. & lift 1.5 mtr.	cum	6.00			
1.4	Stone soling work in foundation with proper levelling and compaction lead 30m.	cum	1.20			
1.5	"Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications"	cum	11.90			
1.6	Providing and laying of Plain Cement Concrete M 15 (or 1:2:4 for nominal mix) in Foundation complete as per Drawing and Technical Specifications formwork included	cum	8.61			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.7	Paving Interlocking concrete block of different shape 60mm thickness (Locally made by Vibrating Machine) in 50 mm sand dust	Sqm	468.00			

Total Item Price	
VAT (13.00%)	
Grand Total	