Bill of Quantities (BOQ)

Upgrading of Gagre Bhanjyang Jitpur Soyak Belase Road (Kharayo danda to Maikhola -6km)

IFB No.: 3370103011/IDOILAM/NCB/W/14/83/84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for loss or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data and technical specifiation (Cl. 19 of CoC)	PS	1.00	17,000.00 Seventeen thousand rupees only.	17,000.00 Seventeen thousand rupees only.
PS.2	Providing, writing and installation of the project information board as per the Standard Specifications and approved drawings and as instructed by the Engineer.	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				19,000.00 Nineteen thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Road way Excavation in all types of soil including ordinary soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.by Mechanical Means	Cum.	2,053.6126			
1.2	Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications Mechanical method, lead upto 30 m	Cum.	38.7874			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum.	291.50			

Total Item Price	
VAT (13.00%)	
Grand Total	