Bill of Quantities (BOQ)

Ratna Rajnarg Shining Star School Dekhi Sital Nagar Naya Basti Hudai Jharkatti Staronnoti, Kohalpur-08, Banke.

IFB No.: 801055702/BANKE/KOMUN/W/NCB-02/2083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Provisional Sum	PS	1.00	0.00 Zero rupees only.	0.00 Zero rupees only.
	Total provisional sums				0.00 Zero rupees only.

General item

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property.	PS	1.00			
1.2	Carry out additional tests for material and works as required and instructed by the Project Manager.	PS	1.00			
1.3	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specifixcation for Road and Bridge Works.	Nos.	1.00			

Pavement Works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
2.1	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications	m2	5,125.00			

Pavement Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.2	Providing, laying, spreading, watering, levelling and compaction of natural sand gravel subbase grading as per table 12.1 of standard specification lead upto 10m.	m3	668.25			
2.3	Providing, laying, spreading, watering, levelling and compaction of crusher run materials for base course lead upto 10m. (a) Machine works	m3	607.13			
2.4	Providing and spraying bituminous prime coat MC30/MC70 including cleaning the road surface using wire, brushes, broom etc. all complete before applying prime coat. (1301 .1302)	Ltr	3,642.75			
2.5	Providing and spraying bituminous tack coat MC30/MC70 including cleaning the road surface using wire, brushes, broom etc all complete before applying tack coat (1301.1302)	Ltr	2,385.00			
2.6	Providing mixing, laying, compaction etc allcomplete of 40mm thick bitumenosus asphalt concrete.	cum	148.50			
2.7	Providing and laying of hot applied thermoplastic compound at least 2mm thick including reflectorizing glass beads asper DOR Traffic sign manual/ Specifications. The finished surface to be level, uniform and free from streaks and holes.	Rm	2,445.00			

Road Side Drain Work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
3.1	Roadway excavation / Back cutting in all types of soil and rock including disposal of excavated materials to suitable place all complete as per specification. [Spc. 905]	cum	1,156.00			

Road Side Drain Work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
3.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum	378.00			
3.3	PCC for RCC(1:2:4)works	cum	799.43			
3.4	Reinforcement work	Kg	23,977.04			
3.5	Backfilling work	cum	1,476.00			

Total Item Price	
VAT (13.00%)	
Grand Total	