Bill of Quantities (BOQ)

Construction of Barha Bigha Fencing work of Shree Mohan Secondary School Mirchaiya

IFB No.: 801021605/4-MM-2083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance Premium and Lab test (as per instructions of site engineer)	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Provide, erect and maintain project site notice board as specified.	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				55,000.00 Fifty-five thousand rupees only.

Fencing wire CPV: 44312000-0 - Fencing wire						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Surface dressing works including cutting grass, uprooting, cuttuing moulds, levelling, dressing of constrution site all complete works as per specification and or instruction of site incharge.	Sqm	616.00			
1.2	Earthwork in excavation including a lead of 10m and a lift of 1.5m all complete works as per specification and or instruction of site incharge.	Cum	12.70			
1.3	Plain Cement Concrete for RCC works: M15 strength grade concrete for foundation and other structures with approved quality of cement (ordinary portland cement), sand and stone crushed aggregate (10-20mm) including mixing, transporting, placing, compaction, curing etc. including cost of all materials, all complete as per specification,drawings and instruction of engineer.	Cum	12.70			
1.4	Fabricating,supplying & fixing work of 50mm Ms Black pipe @ 8'c/c gap with height 6'-6" with prime coat & top cover	Kg	4,461.07			

Fencing wire **CPV: 44312000-0 - Fencing wire**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Fabricating,Supplying & fixing work of 10SWG GI chain link(3"x3") mesh size.	Sqm	1,539.16			
1.6	providing and fixing MS Gate as per Drawing with 50mm x 50 mm x 3mm MS angle,25 mm x 25 mm MS square pipe, 16 gauge MS Flat Sheet, 12 mm x 3 mm Flat, ready made pivot hing welded to 175mm long angle hold fast embedded in 100 mm MS black pipe and iron locking arrangement over one coat primer(@35kg/sqm)	Kg	703.15			
1.7	Two coat of prepared Aluminium painting work over single coat of primer including supply of materials according to drawing and specification and instruction of site incharge as all complete.	Sqm	170.73			

Total Item Price	
VAT (13.00%)	
Grand Total	