Bill of Quantities (BOQ)

Saptari Chetra no-1, Agnisair Krishna Samran ward no.1 sabik jandol 1,3,4,6,7 bato storannati, saptari chetra no.1 tirhut ga.pa.-1 ma trikaul ko rameshko khaet dekhi arji school samma dhalan karya.

IFB No.: 3370115012/IFB-01-83-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss or damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as described in Condition of Contract .	PS	1.00	55,000.00 Fifty-five thousand rupees only.	55,000.00 Fifty-five thousand rupees only.
PS.2	Provding, erection of project information board (size: 1.8mx1.2m) in flex print , in 50mm dia tubular steel post, all complete	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.3	Provide, operate and maintain quality control laboratory including quality control engineer equipment, accessories and consumables for both field testing facilities and off site test with manpower along with transportation facility for employer as per specification as instructed by engineer.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				1,10,000.00 One lakh ten thousand rupees only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Construction of Embankment with Material obtained from Borrow pits. Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.	cum	196.3875			
1.2	Providing and laying Granular Sub-Base Material. By Mechanical means . Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications.	cum	201.76875			

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	Scarifying Existing road Surface to a depth of 50 mm by Mechanical Means.Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications.	sqm	1,213.75			
1.4	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.including formwork Grade M 20	cum.	201.76875			
1.5	Providing and laying , fitting and placing un-coated reinforcement complete in Superstructure as per drawing and technical specification and Engineers instructions all complete.(SS-2014)	Kg	10,759.259			
1.6	Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications and Engineers instruction all complete.(SS-701) Pipe culvert (60 cm)	Rm	7.50			
1.7	Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications and Engineers instruction all complete.(SS-701) Pipe culvert (90 cm)	Rm	5.00			
1.8	Providing and laying Stone Masonary work in cement motar 1:4 in structure including 110mm diameter HDP pipe for weep holes @ 1 no per sqm all complete as per drawing and technical specification and Engineers instruction all complete.(SS-2600)	cum	22.92			
1.9	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications and Engineers instruction all complete. (SS-907)	cum	10.26			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.10	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and Engineers instruction all complete.(SS-2106)	cum	2.43			
1.11	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications and Engineers instruction all complete.(SS-2000)	cum	1.21			
1.12	Providing 12mm Plywood for the use of construction joint all complete as instructed by Engineer	sqm	67.546875			

Total Item Price	
VAT (13.00%)	
Grand Total	