Bill of Quantities (BOQ)

Construction & Upgrading of Road, Drain and other structures In Between Laligurash & Hariom Path and Laligurash Path of Ward no. 08.

IFB No.: 801054805/SNP/NCB-11/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Providing and installation of Project Signboards,Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property, Carry out additional tests for material and works,Dismantling of the existing structures (Drain, etc,), Relocation of the utilities (water supply, telephone, etc,) and services,dewatering and other necessary works as instructed by the Engineer as per approved Norms and Technical Specifications.	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
	Total provisional sums				30,000.00 Thirty thousand rupees only.

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing of grass, removing roots breaking sods, leveling the surface and disposal as per drawing,Technical Specification and instruction of site engineer.	Sqm.	506.70			
1.2	Excavation in roadway and drain in all types of soil and rock materials including removal and satisfactory disposal of all materials at approved environmentally safe tipping area all complete as per drawing,Technical Specification and instruction of site engineer.	Cum.	36.33			
1.3	Stone soling work at drain bed as per instruction and specification all complete.	Cum.	18.165			
1.4	Providing and laying of plain cement concrete M15 (or 1:2:4 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.	Cum.	9.0825			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing, laying, spreading embankment with borrow material (Transported Earth) as per Drawing and Technical Specifications.	Cum.	49.0125			
1.6	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. [Mechanical Means]	Cum.	99.935			
1.7	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. [RCC grade M20]	Cum.	78.4325			
1.8	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	Kg	4,116.820099			
1.9	Form work for drain,structures,etc. including supply and selection of materials fixing, nailing according to drawings, placing separa- tors, dismantling forms and hauling upto 30 m distance	Sqm.	341.94			

Total Item Price	
VAT (13.00%)	
Grand Total	