Bill of Quantities (BOQ)

Swathi Chowk dekhi mangalnagar sadak

IFB No.: 80547403/13.SUN/NCB/2083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Necessary Lab Test Work for official purpose.(Regular reports for Quality Assurance of work done shall be under Contractor responsibility)	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
PS.2	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.3	Provide and Installed Project Sign boards	PS	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
PS.4	Other Unseen Miscellenous Works as per approval. (The payment of this item will be done according to submitted original copy ofrelated invoices.)	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
	Total provisional sums				63,000.00 Sixty-three thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications. @ Depth upto 3m (mechanical means)	Cubic Meter	240.08			
1.2	Providing Brick Bat soiling filling in foundation of Drain & structure as per drawings, specification and instruction of the consultant/Engineer, all complete	Cubic Meter	24.45			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of PCC (1:3:6) in foundation all complete with fair finish Formwork as per Drawing and Technical Specifications	Cubic Meter	36.67			
1.4	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes, with fair finish Formwork etc all complete as per Drawing and Technical Specifications. (Mechanical Means)	Cubic Meter	133.38			
1.5	Providing and laying HDPE pipes (dia 250mm-160mm) for drainage outlet ,subsoil drain including perforations and joining ,all complete as per drawing and instruction by Engineer	Running Meter	33.34			

Total Item Price	
VAT (13.00%)	
Grand Total	