Bill of Quantities (BOQ)

Sunwal Nagarpalika ward no:05 hardiya sthit adhuro covered hall nirman nawalparasi & Covered Hall Marmat 5

IFB No.: 80547403/09.SUN/NCB/2083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
PS.2	Lab Test Work including all necessary Test and providing Test Report all complete work as recommended by site engineer	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
PS.3	Other Unseen Miscellenous Works (Electrical fittings) as per approval. (Work Shall be done only on approval of the workorder by client as per approved norms and the payment of this item will be done according to submitted original copy ofrelated invoices)	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.4	Installation of Information board all complete work as recommended by site engineer	PS	1.00	2,500.00 Two thousand five hundred rupees only.	2,500.00 Two thousand five hundred rupees only.
	Total provisional sums				82,500.00 Eighty-two thousand five hundred rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Clearing the site of all the vegetation, roots and other unuseful materials including excavation of top soil to a depth of 15 cm, removing bushes, trees and leveling the Site for stacking the useful items in specified space and disposing other item before commencing the construction work as per instruction of the site engineer all complete including layout of buildings, roads and ancillary services.	SQM	108.55			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Providing and fabricating a different size of iron truss work of approved pattern and manufacture finished with one coat of red oxide & two coat paint with approved colour all completeas per drawing , specification and approval of an engineer.	Kilogram	2,244.48			
1.3	Supply and fitting of 0.50mm Colored CGI sheet roofing including fixing in proper shape & size with all necessary rails, screws, bolts & nuts washers, J & L hoocks/Screws etc as per drawing & instruction all complete.	SQM	352.19			
1.4	Providing, laying & curing 12.5 mm thick cement sand (1:4) Plastering on in Brick masonary walls, beams surfaces including chipping & wetting the concrete surfaces finished in perfect plumb, lines and level as per drawings, specifications and instructions of the site engineer.	SQM	225.00			
1.5	Providing and Stone soiling in foundation and floor as per drawings, specification and instruction of the consultant/Engineer, all complete.	Cubic meter	23.55			
1.6	Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:2:4 (1 cement : 2 sand : 4 coarse aggregate) for leveling course in foundations and floor of building, pathway, etc in all level with stone aggregate of size not more than 25 mm of approved quality dewatering, batching, mixing, transporting, placing, compacting with vibrator, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.	Cubic meter	23.55			
1.7	Providing and fixing in position Fe500 steel reinforcement of various diameter in R.C.C works including straightening, cutting, bending, binding with wire for tying the reinforcement bars at each junctions (binding wire shall not be measured separately) including all waste pieces, provision for adequate numbers of spacers, providing at all levels all complete as per drawings, specifications and instructions of the Engineer.	Kilogram	1,292.26			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.8	Supplying and laying centering, shuttering of various pattern formworks water proof ply wood & steel adjustable props for all kinds of RCC & PCC works for foundations, columns, shear walls, beams, slab, staircase, lintel, sill, pergola, including nails, propping scaffolding, staging, supporting and bracing in proper lines and level, sealing the joints,aligning to line and levels including Ties, PVC Spacer, Providing openings/ cutouts/ pockets,deshuttering as approved by the Engineer etc., complete at all levels as per drawing, specifications and instructions of the Engineer. FOR Concrete Works	SQM	5.54			
1.9	Making and fitting / fixing sal wood Panel door & window shutter of 38mm size sal wood shutter including supply of materials, all necessary hardware fitting all complete as per approved drawing, Specification and instruction of site engineer.	SQM	9.00			

Total Item Price	
VAT (13.00%)	
Grand Total	