Bill of Quantities (BOQ)

Construction of Irrigation Canals and Procurement and Installation of Motors and HDPE Pipes in Different Toles of Parshuram -09, Dadeldhura.

IFB No.: 80775402300/06/WORKS/NCB/PM/2083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, contractor's workmen and employee and third party insurance against damage to other persons and property as per Bidding Document.	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
	Total provisional sums				15,000.00 Fifteen thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation in Boulder mixed and Soft soil in foundation, trenches including timbering and shoring & 30m Lead and 1.5 m. lift all complete as per design, drawing and specification.	Cum	86.79			
1.2	Stone soling work in foundation and floors with supplying of approved quality of stone laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification.	Cum	88.829999			
1.3	P.C.C.(1:2:4) for P.C.C.work in foundation, columns, beams, slabs, lintels etc. with cement, sand, and crushed stone aggregate of size less than 20mm including mixing with concrete mixture, compacting the concrete with vibrator machine, laying, finishing to approved level ,lines and dimensions and curing all complete nett.	Cum	134.33			
1.4	Steel reinforcement bar (grade 415 or above) tested including straightening, cleaning, cutting, bending and fixing in position with 20 B. G. annealed binding wire as per drawing and instruction complete work	Kg	692.50			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Formwork with approved materials for all works necessary propping, scaffoldong, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for Column/Slab/Beam etc. complete work	Sqm	311.23			
1.6	Assemble of machine made mechanically salvaged Gabion and Mattresses produced from double twisted heavy coated GI wire of Hexagonal mesh size 100mm*120mm, with mesh wire 3mm,selvedge wire 3.9mm,lacing wire 2.4mm and stone filling in gabions,lacing and tying of lids including transport and fixing of gabions in position, all complete.	Cum	22.00			
1.7	3Hp Indian Diesel Pump Set	Nos	1.00			
1.8	Heavy-Duty PVC Spiral Suction Hose 50mm	Nos	10.00			
1.9	HDPE Pipe	Kg	1,234.22			
1.10	Gate Valve 40mm	Nos	1.00			
1.11	GI Wash Out 50mm	Rm	0.50			
1.12	GI Inlet Pipe 40mm	Nos	0.50			
1.13	End Cap 50mm	Nos	1.00			

Total Item Price	
VAT (13.00%)	
Grand Total	